BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

NO:BBMP/EE/YNK.D/EPMT-01/2020-21 Dt:02-5-2020

APPROVED TENDER SCHEDULE –'B'

Item 44

Name of Work :-Construction of Garbage flatforms and lachats pipelines at Chikkabettahlli in ward no:03, Attur

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri BHUMIREDDY DAMODAR REDDY	
				Rate	Rate in Words
1	KSRRB 300 - Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	cum	106.37	208.82	Two Hundred Eight Paise EightyTwo Only
2	KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. with all lead and lift etc	cum	49.16	5259.24	Five Thousand Two Hundred FiftyNine Paise TwentyFour Only

	SRB 4-1.5 : Providing and laying in osition plain cement concrete of Mix M20 w OPC @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.43cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications. with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	cum	49.69	5478.25	Five Thousand Four Hundred SeventyEight Paise TwentyFive Only
4	KSRRB - M2300-14: Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, palcing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining memebrs wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.MORTH Specification No. 1600 & 2200 for TMT bars Fe 500. with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Tonne	0.18	71772.47	SeventyOne Thousand Seven Hundred SeventyTwo Paise FourtySeven Only
5	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete. As per the direction of Engineer incharge. with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Nos	231.00	419.51	Four Hundred Nineteen Paise FiftyOne Only
6	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 Specification No. KSRRB M800-6. with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Sqm	31.20	419.51	Four Hundred Nineteen Paise FiftyOne Only

	SRB 5-14 : Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Sqm	14.40	950.06	Nine Hundred Fifty Paise Six Only
8	KSRB15-3 : Providing 15mm thick cement plaster in single coat with cement mortar to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. I.No.15.13, with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Sqm	14.40	227.23	Two Hundred TwentySeven Paise TwentyThree Only

Signature of the Contractor

B. Dharmeshwa

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.